

Sustainable Contingency Base Camp Operations and Management: Observations in Afghanistan 2011

Garth Anderson, P.E.

Construction Engineering
Research Laboratory

E2S2 Conference

New Orleans, LA

11 May 2011



US Army Corps of Engineers
BUILDING STRONG®



| Report Documentation Page | | | Form Approved OMB No. 0704-0188 | | |
|--|------------------------------------|-------------------------------------|---|---|---------------------------------|
| Public reporting burden for the collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington VA 22202-4302. Respondents should be aware that notwithstanding any other provision of law, no person shall be subject to a penalty for failing to comply with a collection of information if it does not display a currently valid OMB control number. | | | | | |
| 1. REPORT DATE 11 MAY 2011 | | 2. REPORT TYPE | | 3. DATES COVERED 00-00-2011 to 00-00-2011 | |
| 4. TITLE AND SUBTITLE Sustainable Contingency Base Camp Operations and Management: Observations in Afghanistan 2011 | | | | 5a. CONTRACT NUMBER | |
| | | | | 5b. GRANT NUMBER | |
| | | | | 5c. PROGRAM ELEMENT NUMBER | |
| 6. AUTHOR(S) | | | | 5d. PROJECT NUMBER | |
| | | | | 5e. TASK NUMBER | |
| | | | | 5f. WORK UNIT NUMBER | |
| 7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) Army Engineer Research and Development Center, Construction Engineering Research Laboratory, PO Box 9005, Champaign, IL, 61826-9005 | | | | 8. PERFORMING ORGANIZATION REPORT NUMBER | |
| 9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) | | | | 10. SPONSOR/MONITOR'S ACRONYM(S) | |
| | | | | 11. SPONSOR/MONITOR'S REPORT NUMBER(S) | |
| 12. DISTRIBUTION/AVAILABILITY STATEMENT Approved for public release; distribution unlimited | | | | | |
| 13. SUPPLEMENTARY NOTES Presented at the NDIA Environment, Energy Security & Sustainability (E2S2) Symposium & Exhibition held 9-12 May 2011 in New Orleans, LA. | | | | | |
| 14. ABSTRACT | | | | | |
| 15. SUBJECT TERMS | | | | | |
| 16. SECURITY CLASSIFICATION OF: | | | 17. LIMITATION OF ABSTRACT Same as Report (SAR) | 18. NUMBER OF PAGES 49 | 19a. NAME OF RESPONSIBLE PERSON |
| a. REPORT unclassified | b. ABSTRACT unclassified | c. THIS PAGE unclassified | | | |

OUTLINE

- DEFINITION
- BASE CAMP DEFINITION & FUNCTIONS
- STAFFING – Examples in practice
- TRAINING
- POLICIES AND PRACTICES
- RECOMMENDATIONS



BASE CAMP DEFINITION

“A *base camp* is an evolving military facility that supports the military operations of a deployed unit and provides the necessary support and services for sustained operations. Base camps consist of intermediate staging bases and forward operations bases and support the tenants and equipment. While base camps are not permanent bases or installations, they develop many of the same functions and facilities the longer they exist. A base or base camp can contain one or more units from one or more Services. It has a defined perimeter and established access controls and takes advantage of natural and man-made features.”

TRADOC Base Camp Functional Area Analysis



That which we call a *BASE CAMP*
by any other name would smell as bad.

NON-TRADITIONAL INSTALLATION

MOB

CSL

AIRFIELD

COP

FOB

COS

CMB

JFOB

JCOB

COL

THEATER ENCAMPMENT



BASE CAMP CORE FUNCTIONS

- Command & control
- Life support
- Force protection
- Power projection
- Fires support
- Communications support
- RSOI support
- Maintenance & logistics support
- Transportation support
- Training support
- MWR
- Emergency Services



WHY SUSTAINABLE BASE CAMPS?

- Reduce resource consumption
 - ▶ Fewer vehicles and soldiers on the road
 - ▶ Lower cost
 - ▶ Reduce basecamp footprint
 - ▶ More resources = larger logistics tail that also must be supported
 - ▶ More supportable in austere locations
- Human health & environment
 - ▶ Enhance soldier quality of life
 - ▶ Less impact on local economy and culture
 - ▶ The right thing to do!



ACHIEVING SUSTAINABILITY

- Staffing and Management
 - ▶ Base camp staff manning and organization
 - ▶ Training
- Methods and Standards
 - ▶ Doctrine, policies and practices
 - ▶ Master planning
 - ▶ Construction techniques and standards
 - ▶ Quality of life standards
- Technology
 - ▶ Efficient power generation, distribution, usage
 - ▶ Water reuse



BASE CAMP STAFFING AND TRAINING




BUILDING STRONG®

MANEUVER ENHANCEMENT BRIGADE – *Good!*

- TF Rushmore (196th MEB) managed Kabul Base Cluster (7 camps)
- Large, multi-functional staff
- Separate LTC-led mayor cell for each larger camp
- Robust DPW supported entire KBC



MANEUVER ENHANCEMENT BRIGADE



REGIONAL SUPPORT GROUP


Good!

- 645th RSG staffed US portion of Kandahar AF
- Colonel-led, provided appropriate rank to work with NATO staff
- Augmented DPW staff
 - good skill set
- Attached contracting cell



RSG STRUCTURE

(Draft, Proposed)



BRIGADE COMBAT TEAM



Good effort, Wrong unit

- TF Archer (38th IBCT) managed Bagram AF, population > 30,000. *Did an excellent job playing the hand dealt.*
- TF also responsible for ISAF missions
- BDE SPT BN CDR dual-hatted. Most time spent on mayor responsibilities, little time to oversee ISAF mission support companies
- Augmented DPW, civilian master planner
- Large enduring base needs dedicated base camp manning



Commander: LTC John Perkins
CSM: CSM Willie Adams

TF Archer



SMALL BASE CAMP STAFFING

- FOB Lindsay, population = 1,200, staffed by HQ Troop of Cavalry Squadron
- Mayor staff = 2 X CPT, 1 X MSG, 1 X SFC, 2 X SGT.
Excellent leadership!
- AF EPBS master planner
- LOGCAP element on base for water, power, DFAC, facility maint. AMC from KAF provided oversight.
- Other support from nearby Kandahar AF



TRAINING (or lack thereof)

- Pre-deployment training
 - ▶ Few units received formal training on base camp and DPW operations
 - ▶ No training packages or venues available for training
 - ▶ If unit designated mid-tour to manage base camp, no resources available for OJT: SME contacts, standard processes, etc
- Contracting
 - ▶ Individuals received some COR training but may not have had expertise to oversee contracts
 - ▶ 8 hours on line does not a COR make!



TRAINING: Getting better

- 75th Battle Command Training DIV making effort to integrate base camp operations into pre-deployment command post exercises
- RSGs developing training to support METL of base camp management
- Unit initiative to seek non-conventional training sources
 - ▶ Contacting installation DPWs and Garrison Commands to learn processes
 - ▶ Seeking SMEs for pre-deployment training



METHODS: PLANNING, DOCTRINE AND STANDARDS



BUILDING STRONG®

MASTER PLANNING: *GOOD!*

BIG Improvement in Master Planning

- ▶ Air Force Expeditionary PRIME BEEF Squadrons producing “Ultra-Light” master plans
- ▶ Contains only information critical to commander and mayor staff
- ▶ Updated regularly – no more 200 page masterpieces collecting dust!




BUILDING STRONG®

| Requirement Met | Capacity Increase Planned | Critical Need |
|-----------------|---------------------------|---------------|
|-----------------|---------------------------|---------------|

| Requirement | Existing Capacity | Additional Capacity Required | Remarks |
|-------------------------------------|--|---|---|
| Administration TOC | 5,600 sf hardstand buildings, 7680 sf SWA hut | 2840 sf SWA hut | Project 14 will meet req |
| Airfield HLZ | Landing/parking for 1 Chinook rotary aircraft | Landing/parking for 2 Chinook rotary aircraft | Project 15 will meet req |
| Force Protection Various | Masonry wall perimeter, HESCO where expansion has occurred, guard towers, K-9 facility, ECP, PTDS. | Upgrades to masonry wall adjacent to ANP facility, upgrade to all guard towers , sniper fence | Projects 16 and 17 will meet req |
| Health & Safety Fire Protection | None | To be determined | Project 18 will meet req |
| Health & Safety Medical | Existing Aid Station | Proposed enlarged new clinic to be co-located with Fire Station | Project 19 will meet req |
| Housing Contractor Beddown | Full Logcamp 300 | None | Met |
| Housing Troop Beddown | Tent and Hardstand housing @ current pax of [REDACTED] | [REDACTED] pax total, through construction of (2) LOG-CAMP 300 and re-arrangement of other existing tents | Projects 1 and 2 will meet req |
| Infrastructure [REDACTED] | [REDACTED] | [REDACTED] | Project 11 will meet req |
| Infrastructure Comms | Individual rooms in admin bldgs. | Tactical Sensitive Communication and Information Facility (TSCIF) and overall comm. Ring | Project 6 will meet req |
| Infrastructure Firing Range | 25 meter range | None | Met |
| Infrastructure [REDACTED] | [REDACTED] | None | Met |
| Infrastructure Motor Pool | Parking and service for approx. 200 vehicles | Reconfiguration of SE corner of FOB for motor pool and maintenance compound to park and maintain approx. 350 vehicles | Project 5 will meet req |
| Infrastructure Roads and Drainage | Primary roadways for travel around the perimeter of the base; surface drainage | Roads providing emergency access to central portions of the base, stormwater drainage channels | Project 4 will meet req |
| Infrastructure Power | Mixture of 50 Hz and 60 Hz generators | 60Hz generators as needed, proposed mini-grid for Bear 550 | As needed |
| Infrastructure Solid Waste Disposal | Burn Pit | Incinerator to sort and dispose of solid and biomedical waste. Haz Mat storage facility | Project 13 will meet req |
| Infrastructure Storage | CONNEX, Class I, Class IV | SSA admin facility (dedicated SSA storage and distribution facility with administrative processing space) | Projects 9 and 10 will meet req. |
| Infrastructure Wastewater | Currently trucked off base | Sewage collection system to consolidate collection points | Future project will meet req. |
| Infrastructure Water | Existing well producing insufficient yield relative to current PAX | 2nd well | Project 8 will meet req |
| LSA Support Dining | Bear 550 DFAC | [REDACTED] pax hardstand DFAC | Project 7 will meet req |
| LSA Support Various | MWR, Laundry Facility, Gym, Barber, add'l LSS facilities | Additional Laundry Facility, Expansion of MWR and Gym, PX, and hardstand LSS facilities | Project 3and other future projects will meet reqs |

- **777:** Obtain JFUB approval and plan and design projects. Provide construction management for RCC-built projects.
- **3-NCR:** Determine project execution priorities and methods (troop labor versus RCC)
- **USFOR-A:** Receive and validate LOJs, coordinate enduring needs at base.
- **Redhorse/ th En/NMCCB :** Troop labor for project construction.
- **RC- :** Oversee selection of contractors to complete RCC projects.

- Infrastructure/facilities will typically be austere, functional, and practical, and simple, solid, and safe: the most basic solution that fully meets the need over the anticipated period of use.
- Intended to make most efficient use of limited resources - time, money, people, material - while meeting mission objectives.
- Established by US and NATO orders: FRAGO , OPLAN , NATO , /SHLEX/
- MMR planning/design factors: (1) availability of materials/real estate;(2) construction capabilities;(3)ability to use an existing versus a new asset;(4)mission duration and function;(5) geography/topography; and(6)relevant civil development objectives.

Province, Afghanistan

Region: RC- [redacted]
 October 20 PAX: [redacted]
 Land Boundary Area: 72 acres
 Perimeter: Majority HES TO ALA Masonry wall
 LUA Status: approved, expansion pending
 Prevailing Wind: NW
 LOGCAP Band: 4
 Mine Clearance: All areas within perimeter cleared



- Originally developed to support


- In late _____, the base was expanded under _____ as BOS-I to its current boundaries, to accommodate an anticipated troop level increase when _____
- _____ assumed BOS-I in early 20_____, and began programming a variety of improvements
- BOS-I transferred to _____ in the summer of 20_____, and efforts began to organize and consolidate the projects initiated by _____
- A second expansion of the FOB is expected to be approved in early 20_____. Master planning efforts for this area are just starting to commence

- U.S. upgrading facilities to support pax increase up to _____ and to accommodate mission emphasis on battlefield support
- A portion of the south central part of the base supports enduring efforts with xx personnel


- Serves as hub for U.S. forces supporting and conveying to adjacent COP's
- Serves as support for

•
•
•
•
•
•

| Unit | O/H | 15 Jan |
|------|-----|--------|
|------|-----|--------|



Proposed Master Plan



Development Constraints and Initiatives

- Accommodate pax increase up to [redacted] troops within limited FOB area constrained by adjacent residential development
- Support FOB mission focus on battlefield support, including distribution of materiel and equipment for troops deploying to adjacent COP's/checkpoints
- Consolidate compatible land uses in appropriate locations
- Integrate proposed expansion to maximize FOB capacity and functionality
- Enhance AT/FP elements to accommodate proposed FOB expansion, given the proximity to [redacted]

Site Imagery / December [redacted]

LSA 1, east of Bear DFAC looking north



South of new DFAC construction site looking north




Key Development Projects



| Proj # | IJC # | Title/EPN | Description | Construction Method | Status |
|--------|-------|--|---|--------------------------------------|---------------------------------------|
| 1 | 7 | Logcamp 300/E11-0531 | Acquisition and construction of a Logcamp 300 to replace worn out billeting assets | TBD | Awaiting JFUB |
| 2 | 7 | [2] Logcamp 300/E11-0502 | 2 Logcamp 300 sets to provide billeting and LSS's for an anticipated increase in pax | TBD | Awaiting JFUB |
| 3 | 7 | Hardstand LSS Units/No JFUB # assigned | Construction of 3 CMU LSS facilities to support new billeting compounds | RCC | Under Construction |
| 4 | 7 | Roads and Drainage/E11-0053/111-0137 | Drainage assessment, grading, and road layout design | Troop Labor | Final Design |
| 5 | 7 | Motor Pool and Maintenance Compound/E11-0453 | Site clearing, fencing, and installation of concrete pads and maintenance shelters for mission essential vehicles and equipment | Troop (site prep) TBD (construction) | Design Review |
| 6 | 7 | TSCIF/E10-1454/110-1474 | Construction of a TSCIF communication hub | TBD | Final Design |
| 7 | 7 | DFAC/110-0863 | 1500 Pax hardstand DFAC to replace original, worn out DFAC | LOGCAP | Under Construction |
| 8 | 7 | Well #2/E11-0401/111-0070 | Construction of a 2nd water well to provide adequate water supply to the FOB | Troop Labor | Under Construction |
| 9 | 7 | Class IV, Maint, Container Yards/E11-0077 | Site prep and construction of fenced Class IV yard, maintenance yard, and container yard in future expansion area | TBD | Design Review |
| 10 | 7 | SSA Facility/E11-0504 | Construction of SSA facility to support 3 BCT activities in and around Kandahar City | TBD | Awaiting JFUB |
| 11 | 7 | | | TBD | Awaiting JFUB |
| 12 | 7 | Base Expansion/E11-0269 | Proposed FOB expansion 200 yds north and 300 yds west, to increase size from 73 ac to 149 ac | TBD | LARP signed, awaiting action in Kabul |
| 13 | 7 | Material Transfer Yard/Incinerators 111-0106 | Site prep and construction/ install sorting facility and incinerators in expansion area | Troop/LOGCAP | ONS #10-694/ Design Review |
| 14 | 7 | Company/Battalion TOCs/111-0305, 110-1468-1470 | 116x32 SWA Hut and 3 32x120 SWA Huts for admin purposes | Troop Labor | Under Construction |
| 15 | 7 | New HLZ/E11-0354 | New HLZ in expansion area capable of landing two CH 47 Chinooks simultaneously | TBD | Design Review |
| 16 | 7 | Sniper Screen/111-0250 | Addition of fencing and screening to the top of the perimeter wall around the FOB. | TBD | ONS #10-859 |
| 17 | 7 | Guard Towers/E11-0364/111-0068 | Replace inadequate guard towers with upgraded facilities | Troop Labor | Under Construction |
| 18 | 7 | Fire Station/E10-1413 | Fire Station per recommendation of USFOR-A | TBD | Pre-JFUB Hold |
| 19 | 7 | Aid Station/E11-0500 | New, larger hardstand Aid Station adjacent to relocated HLZ | TBD | Awaiting JFUB |



FOB [redacted]
Department of the Air Force / 777th Expeditionary Force Base Squadron
Kandahar Airfield, Afghanistan APO AE 09035
(01/10/10)



MASTER PLANNING SUCCESS:

Camp Leatherneck

- Started from scratch – not a captured facility
- Planned as an enduring facility from the beginning
 - ▶ No space restrictions
 - ▶ Permanent facilities from the start
 - ▶ Basic infrastructure in place before buildings
 - ▶ Wide utility corridors planned along roads
- Solid waste incinerator nearing completion
- Graywater separation



MASTER PLANNING SUCCESS:

Camp Leatherneck



CONTINUITY OF OPERATIONS



- Base camp units rotate in total every 9-12 months with 1 week between incoming and outgoing
- Large loss of continuity in process, contract oversight, policy, requirements
- ✓ Some units trying staggered rotations to increase overlap and situational awareness



LOCAL CONSTRUCTION STANDARDS

A Smart Approach



- FOB Salerno constructing standard buildings using local materials, labor and techniques
- Multiple uses – offices, billets, clinics



CONSTRUCTION FEATURES

- Standard building footprint and exterior envelope
- Interiors can be adapted for any purpose with non-load bearing walls or partitions
- Thick walls increase R-value and force protection
- Electrical wiring uses surface mounted conduit
 - ▶ Facilitates quality assurance inspection
 - ▶ Can be easily retrofitted to local standards after base turnover
- Simple “Chigo” split HVAC units, locally purchased



LOCAL MATERIALS AND CONSTRUCTION TECHNIQUES

- Easier to go “Afghan First”
- Reduces transportation costs
 - ▶ Bricks & tiles produced nearby
 - ▶ Concrete placed on site
- Larger construction labor pool – no need for skills in US construction techniques
- Materials are more appropriate for climate
- Structures are culturally suitable for turnover of base





Finished structures





Concrete column prep



Installing roof beams



BUILDING STRONG®



Interior view

Ceiling tiles

Steel tile channels



Roof/ceiling construction



BUILDING STRONG®



Exterior masonry



BUILDING STRONG®



Concrete roof slab prep



Ceiling/roofing tiles



BUILDING STRONG®



Interior finishes



Interior electrical



BUILDING STRONG®

CONSTRUCTION PRACTICES: Good



Innovative techniques

- ▶ Reuse of shipping containers
- ▶ K-Span
- ▶ Frame Master



CONSTRUCTION PRACTICES:

Needs improvement

- MILCON process and timeline do not overlay well in a contingency environment
 - ▶ 2-4 years from requirement definition to groundbreaking
 - ▶ Several rotations of base camp staffs may not have awareness of project in pipeline
 - ▶ MILCON timelines lag far behind bona-fide requirement changes
- Not enough standardization of facilities - tenant units want “custom” buildings



CONSTRUCTION PRACTICES:

Needs Improvement

- We continue to apply US standards even for Afghan occupied facilities
 - ▶ Makes finding licensed contractors difficult
 - ▶ Locals cannot maintain US spec equipment
- From scope of work for Afghan Uniformed Police Station:
 - ▶ Specs in English units
 - ▶ Electrical specs are NEC 2008 and US 120V/60 hz
 - ▶ Fire code is NFPA 2009, including smoke detectors



WATER DEMAND: The Smart



- Graywater capture at some bases
- Reuse for construction and dust control
- Reduces water demand
- Reduces load on WWTP




WATER DEMAND: Needs Improvement

- Mandatory use of ROWPU when standard water treatment works
- ROWPU
 - ▶ Expensive
 - ▶ Costly to operate
 - ▶ Increases water demand by 20-30%



WATER DEMAND: Needs Improvement



- Bottled water remains the primary source of drinking water
- Larger bases capable of producing bulk potable water
- Must overcome bias toward the bottle



WASTE WATER: The Good



- Package plants are effective in areas with limited space
- Standard treatment train: aeration-clarifier-sludge digester-chlorination
- Each unit processes up to 30Kgal/day



WASTE WATER: Needs Improvement

- Many septic fields are ineffective due to limited space and low soil percolation
- Lagoons are typically undersized
- Several bases pump blackwater into trucks for off-base disposal



SOLID WASTE: The Good



- Most bases made effort to recycle
- Burn pits were adequately managed at larger bases
- Waste streams segregated
- Incinerators coming on line



SOLID WASTE: The Good



SOLID WASTE: Needs Improvement

- Urban base camps had few alternatives to haul and dump
- Recycling of plastic not cost effective at smaller bases – no market near



NON-TACTICAL (ADMIN) VEHICLES

Where did they all come from?



- Use of SUVs, ATVs on base is out of control – regular traffic jams
- Majority of trips were for convenience
- US population at KAF
 - ▶ People 20,000
 - ▶ Admin vehicles 6,000
- ✓ Bagram did have bus service



RECOMMENDATIONS

- Large, enduring bases should have permanent base camp staff. IMCOM led?
- Continue to staff large expeditionary bases with either an MEB or RSG
- Develop pre-deployment training packages
 - ▶ Exercise mayor staff during command post exercises
 - ▶ DPW course for contingency camps – not the same as CONUS DPW
 - ▶ Contingency contracting training, also include technical training for specific contract



RECOMMENDATIONS

- Use appropriate water treatment methods based on mission and conditions at specific base camp
- Reserve bottled water for only mission personnel at bases that produce bulk potable water
- Apply graywater separation and reuse systems at more bases.
- If space and soil conditions limit the use of lagoons and septic fields, plan to use WW package plants
- Look at Net Zero Water concepts.



RECOMMENDATIONS

- Units should consider a staggered Transfer of Authority.
- Continue the use of the new “ultra-light” master plan in theater
- Mandate the use of local construction techniques and materials where feasible.
- Limit using US specs for Afghan owned/operated facilities
- Limit the use of administrative vehicles



CONTACT INFORMATION

An aerial photograph of a large military logistics or supply base in a desert environment. The base features several long, two-story yellow buildings with white roofs. Numerous shipping containers in various colors (blue, red, green, yellow) are stacked in rows. Several military vehicles, including trucks and tanks, are visible on the paved roads and in the open areas. The background shows a flat, arid landscape with some distant structures.

COL Garth Anderson, P.E.
Garth.Anderson@us.army.mil
217-419-9091